

## LS lab 3: CI/CD Infrastructure

In this lab, we will focus on how to set up CI/CD infrastructure by deploying Gitlab on-premise:

- Self-managed Gitlab server
- Gitlab Runner
- Deployment server
- CI/CD pipeline
- Web application with test case

### Task 1: Infra Deployment

1. Deploy three VMs that you will be using as Gitlab Server, Gitlab Runner, and the deployment server. Make sure VMs can reach each other.
2. Set up **Gitlab Server** (VM1), create a docker-compose file with below configs:
  - a. Pull the Gitlab EE or CE edition
  - b. Name the running container as <stx>-gitlab
  - c. Map container ports 80 and 22 to host machine
  - d. Expose the Gitlab server as <stx>.sne.com. (Hint: find the right env variable to pass to the container to update the configs of Gitlab. Update the *hosts* file to resolve the mentioned DNS record)
  - e. Bind the necessary directories of the Gitlab server container to host machine (e.g. logs, app data, configs...)
  - f. Run the docker-compose file and make sure the configs are working.
  - g. Access the Gitlab server and log in, create a project name it as <stx>-repo.  
Note: you can also check <https://docs.gitlab.com/ee/install/docker.html>
3. Set up the **Gitlab Runner** (VM2), don't use the docker approach this time.
  - a. Install and configure shared Gitlab Runner
  - b. Explain what is the Gitlab runner executor and set the executor type to *shell*
  - c. Set Gitlab Runner tag to <stx>-runner. (You will be using this tag in the pipeline in the coming task)
  - d. Authenticate your Gitlab runner with Gitlab server, and validate.  
Note: you can also check <https://docs.gitlab.com/runner/install/>
4. Set up the **Deployment Server** (VM3).
  - a. Set up SSH connection such that your Gitlab runner should be able to run scripts on the deployment server.

### Task 2: Create CI/CD Pipeline

1. Clone the project you have created in step **1.2.g**.
2. Write a simple web application in any programming language. (E.g. Random text or Addition of two numbers)
3. Create CI/CD pipeline (.gitlab-ci.yml)
  - a. CI stages of the pipeline should:
    - i. Build the application

- ii. Run test (to check the application works ok)
    - iii. Build docker image (Note: you need Dockerfile)
    - iv. Push to your docker hub account.
  - b. CD stages of the pipeline should:
    - i. Pull the docker image and deploy it on deployment server
- 4. Validate that the deployment is successful by accessing the web app via the browser on deployment server side.

### **Task 3: (Bonus)**

- 5. Update the CD stages to be able to deploy the web applicate using Ansible.
- 6. Update the pipeline to support multi-branch (e.g. master and develop) and jobs should be triggered based on the specific target branch.
- 7. Update keywords such as cache, artifact, needs, and decencies to have more control of pipeline execution.